

PROJECT:  
ADDRESS:  
SECTIONS: ALL

PROJECT FILENAME: TAKE OFF  
ARCHITECT:

Metal Panels Summary

120.00' X 16.00" 16" Wide Panel

LINEAR FEET	QUANTITY	% WASTE	TOTAL LN. FEET	SQUARE FEET
15'8"	25	5.2	391'8"	522.2
11'4"	24	2.1	272'0"	362.7
8'10"	1	8.2	8'10"	11.8
8'7"	1	8.4	8'7"	11.4
7'4"	1	9.9	7'4"	9.8
7'2"	1	10.1	7'2"	9.6
6'6"	10	8.5	65'0"	86.7
5'11"	1	12.2	5'11"	7.9
5'9"	1	12.6	5'9"	7.7
5'8"	2	12.7	11'4"	15.1
5'1"	2	14.2	10'2"	13.6
4'6"	1	9.9	4'6"	6.0
4'5"	2	16.4	8'10"	11.8
4'4"	20	0.8	86'8"	115.6
4'2"	2	17.3	8'4"	11.1
4'1"	8	0.0	32'8"	43.6
* 4'0"	22	37.2	88'0"	117.3
-----			-----	-----
SUBTOTAL	124 Panels		1022'9"	1363.7

\* Minimum Length Panel Breakout:

- 6 X ((1 X 3'8"))
- 2 X ((1 X 2'11") + (1 X 0'9"))
- 4 X ((1 X 2'9") + (1 X 0'9"))
- 4 X ((1 X 2'9"))
- 2 X ((1 X 2'2") + (1 X 1'6"))
- 2 X ((1 X 2'2") + (1 X 1'4"))
- 2 X ((1 X 2'2"))

PAN. TOTAL	124 Panels	1022'9"	1363.7
=====			

Details Summary

DETAIL	UNITS	ORDER INFO
Headwall Detail	18.9 LN FT	
Sidewall (Rakewall) Detail	50.6 LN FT	
Rake Detail	106.9 LN FT	
Eave Detail	124.3 LN FT	
Valley Detail	41.3 LN FT	
Hip Detail	7.5 LN FT	
Ridge Detail	73.1 LN FT	

Total Surface Area = 1261.23 SQR FT

